

City of Canton

Salt Bin Project

Addendum No. 1

Site Preparation. The contractor will be responsible for preparing an 80'x100' site for the 40'x60' salt storage building. The exact location for the site will be determined by the owner and the four corners of the site will also be staked by the owner.

The contractor will grade and compact the site to make it level and to provide drainage of storm water away from the building site.

Crushed limestone will be spread evenly over the entire 80'x100' site, smoothed and compacted so that a vehicle driven onto it will not leave ruts. All limestone shall be 1" clean and meet MoDOT standards. The crushed stone base for the building concrete slabs shall be as shown on the drawings.